

## PERFORMANCE RESULTS

**O'Reilly Oakstown Environmental Ltd.**

Oakstown, Trim  
Co. Meath  
Ireland

**EN 12566-1**

Part 1: Prefabricated septic tanks  
Results corresponding to the Irish National Annex IS EN 12566-1

### **Oakstown Septic Tank**

---

Material	concrete
Hydraulic efficiency (Annex B)	99.68 %
Nominal capacity (usable volume)	3 m <sup>3</sup> (3,409 l)
Watertightness (water test)	pass
Structural behaviour (calculation)	pass (also wet conditions)
Durability	pass

---

Performance tested by:

**PIA – Prüfinstitut für Abwassertechnik GmbH**  
(PIA GmbH)  
Hergenrather Weg 30  
D-52074 Aachen

Certified according to  
ISO 9001:2008



Notified Body number: 1739



This document replaces neither the declaration  
of conformity nor the CE marking.

Prüfinstitut für Abwassertechnik GmbH  
  
geprüft - tested - testé

Elmar Lancé

October 2012